Phase 1 Habitat Replacement & Reconstruction

Marc Greenberg, USEPA

greenberg.marc@epa.gov







EPA's Expectation of Habitat Reconstruction & Replacement

- Hudson River provides diverse habitats
 - Plants, plankton, aquatic invertebrates, fish, amphibians, reptiles, birds and mammals
 - Animals living in wetlands, floodplains and upland communities are also dependent on the river





Habitat Reconstruction & Replacement (Con't)

- A habitat replacement program is being implemented:
 - To mitigate for impacts to habitats from the remedial activity
 - To reconstruct, replace, and/or stabilize
 - Unconsolidated River Bottom (UCB)
 - Submerged Aquatic Vegetation (SAV)
 - Riverine Fringing Wetland (RFW)
 - Shoreline (SHO)





Unconsolidated River Bottom (UCB)





- Generally non-vegetated
- Habitat for bottom-dwelling organisms





Submerged Aquatic Vegetation (SAV)





- Underwater vegetation
- Serves as habitat for fish and bottom-dwelling organisms






SAV Primary Planting Areas

- Approx 5.7 acres to plant in 2010
- Areas shown are original proposed
- Actual areas to be determined at Spring 2010 pre-planting inspection






SAV Contingency Planting Areas

- Up to approx 7.2 acres
- For use if primary planting areas not suitable in Spring 2010
- If not planted, revert to natural recolonization areas





Riverine Fringing Wetland (RFW)




Wetlands at the shoreline



Habitat for birds, mammals, other aquatic-dependent organisms



RFW Habitat Reconstruction Areas




 Not all RFW to be reconstructed in place

total



Shoreline (SHO)



- Habitat along the terrestrial edge of the river (riparian)
- Stability is important for maintaining habitat integrity
- Many species utilize






SHO Stabilization Measures

Type P Stone — Biolog —

- Installed during dredging
- Less stabilization installed than designed
 - Redrawn (offshore)CU boundaries





2009-2010 Phase 1 Habitat Replacement & Reconstruction Activities Overview

2009:

- Dredging
- Backfill placement (BF)
- Install riverine fringing wetland biologs and erosion fabric (jute mesh)
- Shoreline stabilization





2009-2010 Overview (Con't)

2010:

- Pre-planting inspections of aquatic vegetation beds and fringing wetlands
- Seeding and planting of the SAV and RFW
- End-of-season replantings, if needed
 - "... replace dead or unhealthy plants with plants of the same size and species as specified."







Habitat Replacement & Reconstruction Materials

Backfill

- Three Types
 - Sand
 - Coarse sand
 - Sand + topsoil





Armor Stone

- Type "P" Stone
- Used at shorelines for stabilization

Habitat Replacement & Reconstruction Materials

Biologs, Fabric, and Plants

- 12 inch diam. logs for RFW reconstruction; SHO stabilization
- Jute mesh at RFW
- Plants/Seed at RFW and SAV





Habitat Replacement & Reconstruction: SAV Seedlings and Tubers

Collected in Fall 2008

- Upper Hudson River, North of Glens Falls
- Vallisneria americana (wild celery) was targeted
- Cultured and maintained at a nursery until planting in 2010





Habitat Replacement & Reconstruction: Unconsolidated River Bottom (UCB)




 Nearshore areas restored to pre-dredge bathymetry

- Backfill placement during 2009
- Included unvegetated nearshore & offshore areas





Habitat Replacement & Reconstruction: Shorelines (SHO)



Habitat Replacement & Reconstruction: Shorelines (SHO)

Stabilization at Dredge Cuts (≤119 ft)

- Location specific
- Measures include:
 - Biologs
 - Backfill
 - Type P Armor Stone
 - Wooden Plank

Reconstruction of affected habitat (>119 ft)

- NOT needed in Phase 1
- 119 ft elevation is the CU boundary
- Measures include:
 - Type P Armor Stone
 - Topsoil and Seed Mix
 - Topsoil and live stakes





Shoreline Stabilization Example: Biolog Option




Design Waterline

Dredge Cut at Shore





Shoreline Stabilization Example: Biolog Option



Design Waterline



Habitat Replacement & Reconstruction: Submerged Aquatic Vegetation (SAV)


- Backfill placed in 2009
- Replacement & reconstruction planning:
 - At or near many predredge SAV bed areas
 - Depth & flow considerations
 - Primary planting and contingency areas







Habitat Replacement & Reconstruction: Submerged Aquatic Vegetation (SAV)







Major Activities	Approx. Quantity
Wetland Planting	21,800 Plants
	0.4 Acres to be replaced
Submerged Aquatic Vegetation Planting	57,000 Adult Plants
	8,550 Tubers
	Total of 5.7 Acres





Generalized SAV Replacement & Reconstruction: *Pre-Dredge Conditions*






Generalized SAV Replacement & Reconstruction: Example Dredge Cut







Generalized SAV Replacement & Reconstruction: *Post-Dredge Mudline*



Generalized SAV Replacement & Reconstruction: 1-Ft Backfill Placement




Generalized SAV Replacement & Reconstruction: Supplemental & Nearshore Backfill Placement




Generalized SAV Replacement & Reconstruction Cross-Section:

Planting Followed by Monitoring



Habitat Replacement & Reconstruction: Riverine Fringing Wetlands (RFW)




 Two planting zones above & below 118,5 ft

Major Activities	Approx. Quantity
Wetland Planting	21,800 Plants
	0.4 Acres to be replaced
Submerged Aquatic Vegetation Planting	57,000 Adult Plants
	8,550 Tubers
	Total of 5.7 Acres

Habitat Replacement & Reconstruction: Riverine Fringing Wetlands (RFW)

- Backfill placed during 2009
- Biolog and Jute Mesh Installed 2009

Typical RFW Zone A Seed Mix Spp.



Habitat Replacement & Reconstruction: Riverine Fringing Wetlands (RFW)



Typical RFW Zone B Plants









Habitat Replacement & Reconstruction Timeline: Riverine Fringing Wetland Example



Habitat Replacement & Reconstruction Timeline: Riverine Fringing Wetland Example

In Dredging Year (May-November 2009)

- Remove contaminated sediments
- Place backfill
- Install erosion control blanket and/or biologs

In Following Growing Season (2010)

- Pre-planting inspection to identify final RFW planting areas
- Prepare selected planting areas
- Install plants; monitor for health & desired conditions

Year After Planting (2011)

- Adaptive Management Plan
- Monitoring begins for benchmarks





Habitat Summary

- Approximately 48 acres were dredged and filled in 2009
- SAV habitat prepared for inspection, then planting, in Spring 2010:
 - Primary planting 5.7 acres (approx.)
 - Contingency areas up to 7.2 acres (approx.)
- Approximately 0.4 acre RFW habitat was stabilized and backfilled in preparation for inspection/planting 2010





Habitat Summary (Con't)

 Impacts to shoreline habitats greater than an elevation of 119 ft did not occur in 2009

Shoreline stabilization:

Type P stone: 1,380 linear ft (approx)

Biolog: 1,500 linear ft (approx)

Remaining shorelines stabilized with nearshore BF





Thank You!

Questions?